

SISTEMA SANCAD - PLANILHA DE DADOS FINAIS

25 DE JULHO

TRECHO 2

REVISÃO 02

20/03/2015

L:\EG0185 - REDES ESGOTOS PELOTASIARQ TRABALHO\SANCAD\25 JULHO\REV02\TRECHO 2\SANCAD 25J 5.2.2_REV02.DBF

Coletor	PVM	PVJ	Comp (m)	CTM (m)	CTJ (m)	CCM (m)	CCJ (m)	PRFM (m)	PRFJ (m)	Diam (m)	Decl (m/m)	Q Real Ini (l/s)	Q Real Fim (l/s)	Veloc Ini (m/s)	Veloc Fim (m/s)	Trativa (Pa)	H/D Ini	H/D Fim	Observ.
002-001	25J-005	25J-006	65.00	14.116	13.350	12.116	11.350	2.000	2.000	0.150	0.01178	0.467	0.737	0.70	0.70	1.93	0.18	0.18	
002-002	25J-006	25J-007	60.00	13.350	12.653	11.350	10.653	2.000	2.000	0.150	0.01162	0.898	1.417	0.70	0.70	1.91	0.18	0.18	DG 0.007
002-003	25J-007	25J-008	100.00	12.653	11.291	10.646	9.284	2.007	2.007	0.150	0.01362	1.617	2.550	0.75	0.86	2.23	0.18	0.22	DG 0.022
002-004	25J-008	25J-009	100.00	11.291	12.844	9.262	8.859	2.029	3.985	0.150	0.00403	2.336	3.683	0.54	0.62	1.01	0.29	0.37	
002-005	25J-009	FIM	90.00	12.844	10.000	8.859	8.000	3.985	2.000	0.150	0.00954	2.983	4.703	0.79	0.90	2.21	0.27	0.34	FIM

